

ADDENDUM NUMBER ONE

Date of issue: April 29, 2019

Issued by:

SANTA MARIA PUBLIC AIRPORT DISTRICT
3217 Terminal Drive
Santa Maria, California 93455

Architect's Consulting Service

Richard McKenzie AIA, 1187 Coast Village Road Suite 10-H
Santa Barbara CA. 93108
805-331-6259

PROJECT:

**ROOF REPLACEMENT, ADMINISTRATION DISTRICT OFFICE AND FIRE
STATION
3217 & 3339 TERMINAL DRIVE
SANTA MARIA PUBLIC AIRPORT
SANTA MARIA CA 93455**

To all bidders submitting proposals for the captioned project. This addendum is hereby made part of the contract documents to the same extent as though it were originally included therein and takes precedence over the original documents and addenda.

Acknowledge receipt of the Addendum on the **Bid Proposal page P-3**

A. NOTICE INVITING SEALED BIDS FOR ROOF REPAIR OF TERMINAL BUILDING OBSERVATION ROOD DECK

Item No. 1 Revise paragraph A-11, Mandatory Job Walk, First sentence to now indicate
" A mandatory job walk will be conducted on Tuesday, April 23, 2019 and on Tuesday April 30,
2019. Contractors are required to attend only one Job Walk."

B. SPECIFICATIONS

Item No. 1 **Specification Section 07 54 19 PVC Adhered Thermoplastic Membrane Roof**
Paragraph 2.03 A (1) delete reference to G459 membrane and insert "Sarnafelt where asphalt
contamination exists and membrane to match color of roof field membrane.

Item No. 2 **Specification Section 07 54 19 PVC Adhered Thermoplastic Membrane Roof**
Paragraph 2.03 A (2) Change clad color to now indicate" Grey".

Item No. 3 **Specification Section 07 54 19 PVC Adhered Thermoplastic Membrane Roof**
Revise Paragraph 2.04 B to now read
"B. Coverboard at District Administration Office and Fire Station: Dens Deck Prime. 1/4-inch
thickness."

ADDENDUM NUMBER ONE

Item No. 4 Specification Section 07 54 19 PVC Adhered Thermoplastic Membrane Roof
Delete Paragraphs 2.04 C and 2.04 E in their entirety.”

B. DRAWINGS

Item No.1 Sheet A-3, Key Notes. Revise key note #5 to now read:" Replace existing roof drains with new roof drains and construct new thru wall scuppers at each drain location. See detail 11 on A-5.

Item No. 2 Sheet A-4, Delete detail 7 Roof Scupper Detail. " Note: no parapets exist in the original construction."

END OF ADDENDUM ONE